

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 43N R 15W	F7
	T 43N R 15W	F9
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on F7 02/01/2011 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

(F7) Quarter corner common to Sections 16 and 21. 1973 - reestablished by F.J.Bray RLS, midway and on line between Section corners. Set 1"ID I.pipe with 4" alum. cap. 10" Cedar N85W 44.2', 7" Cedar N86E 35.7'.

(F9) Quarter corner common to Sections 21-28. 1969 - Reestablished by F.J.Bray RLS midway and on line between Section corners east and west. Set 1"ID I.pipe with 4" alum. cap. 5" Cedar N32W 11 links, 7" Cedar N61E 16.5 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(F7) Found the 1973 monument disturbed. Replaced the monument at the 1973 position at record bearing and distance from the 1973 witnesses, both in good condition. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

(F9) Found the 1969 monument in good condition and at record bearing and distance from the 1969 witnesses, both in good condition. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(F7) Set 1" ID I.pipe w/4" alum. cap. (1973 mon)  
 Set measuring nail with MDNR tag in the side of:  
 12" Cedar N80W 44.85' old marks 1973 NBT  
 9" Cedar N87E 35.7' mrkd "1/4S" do  
 8" W.Birch S47E 43.9' mrkd "1/4S NBT"  
 7" Cedar N27W 41.3' do  
 Bearings are magnetic.

(F9) Pd. 1"ID I.pipe with 4" alum. cap.  
 Set measuring nail with MDNR tag in the side of:  
 11" Cedar N63E 11.45' mrkd "1/4S" 1969 NBT  
 11" Cedar N27W 7.3' do do  
 5" W.Birch S59W 8.55' mrkd "1/4S NBT"  
 12" Cedar N09E 26.6' do  
 Bearings are magnetic.

Signed by *Stephan J. Szyszkoski*  
 Surveyor's Michigan License No. 33986

Date 03/08/2011

For the Michigan Department of Natural Resources, Office of Land and Facilities

