

OCT 26 1995

COMMISSION

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

DATE March 10, 1995 LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Schoolcraft (County)

Located In: Corner Code #

- 1. Public Land Survey T 42N R 15W D-1 E-1
T 43N R 15W D-13 E-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Received & Filed this 10 day of March 19 95 at 2:33 PM Sigrid I. Hedberg Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 2-13. Contains numbers 6-36.

I, Thomas P.O'Brien, in a field survey on Nov. 23/24, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-1(North 1/4 Corner Sec.5) Oct.25, 1841 William A. Burt, D.S. set qr. section post Hemlock 12 N51E 7 Do 16 N33W 34

E-1(N.E. Corner Sec.5) Oct.25, 1841 William A. Burt, D.S. set corner post. Hemlock 20 N62E 20 Do 18 N70W 9 Sept.26, 1850 Algernon Merryweather, D.S. Corner 4&5 North boundary Hemlock 7 in S40W 35 links Do 14" S39E 57"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1 Oct.16, 1967 - Frank J. Bray, RLS placed the corner midway and on line to section corners to east and west. No original evidence found. Nov.23, 1993 - Thomas P.O'Brien, PS recovered D.N.R. monument set by F. Bray E-1 Oct.16, 1967 - Frank J. Bray, RLS reestablished the corner by single proportioned measurement and on line between 1/4 corner 1/2 mile to east and town corner 2 miles to west. No original evidence found. Nov.24, 1993 - Thomas P.O'Brien, PS recovered D.N.R. monument set by F. Bray

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1 1" pipe w/4"aluminum cap stamped to identify. 12" Cherry N1W 677.35' (NBT) Note: Area has been clearcut and roller chopped. Bray witnesses have been destroyed and witness trees used are only available trees in area. 10" Cherry N87E 453.15' (NBT) 10" Aspen S10E 223.0' (NBT) Post North .90' E-1 1" pipe w/4" aluminum cap stamped to identify. 6" Jack Pine S60W 17.25' (NBT) Note: Bray witness trees have been cut. Stumps are present 6" Jack Pine S80W 42.70' (NBT) 6" Jack Pine N30W 52.35' (NBT) 6" Jack Pine N3W 34.50' (NBT)

Signed by Thomas P. O'Brien, PS Date March 10, 1995 Surveyor's Michigan License No. 21274

