

SCHOOLCRAFT COUNTY <sup>JOB</sup>  
 PEER GROUP APPROVED

DATE 9/13/96

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

Surveyor's  
 REMONUMENTATION

NOV 21 1996

COMMISSION

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T42NR15W T43NR15W T___R___ T___R___	M-1 M-13 ✓ _____ _____
2. Property Controlling in Section	S___ T___ R___ S___ T___ R___	_____ _____
3. Miscellaneous Property in Sec.	S___ T___ R___ S___ T___ R___	_____ _____

Received & Filed this 30 day of  
Oct 1996 at 11:34 AM  
 Sigrid I. Hedberg  
 Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Thomas P. O'Brien in a field survey on April 2, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-1 (N.E. Corner Sec. 1)  
 Sept. 11/50 Algernon Merryweather D.S. set T. Corner between 42&43 North, Range 15 West.  
 Spruce 8 N75E 8 do. 8 S79W 17

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-1 May 23, 1961- Billy D. Buckler, RLS set a 1" pipe with brass cap at the Township corner ( Towns 42-42 North and Range 15 West.) Corner was re-established using section corners 1 mile South; 1 mile East; 1 mile West and 6 miles North."

April 2, 1996- Thomas P. O'Brien P.S., recovered a 1" pipe with 4" brass cap as set by Billy D. Buckler on May 23, 1961.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1 Found Mich. Dept. of Cons. 1" pipe with 4" brass cap stamped to identify.

Witnesses: Fd. 10" Red Pine- S61°W - 21.80' Ex. Cond.  
 Fd. 12" Red Pine- N16°W - 41.40' Ex. Cond.  
 8" Red Pine- N55°E - 13.82' NBT  
 8" Red Pine- S53°E - 42.95' NBT  
 4" Cedar Post - North - 2.0'

*Thomas P. O'Brien*

Signed by Thomas P. O'Brien  
 Surveyor's Michigan License No. 21274

Date April 2, 1996

