

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>43W</u> R <u>15W</u>	<u>18</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>23</u> T <u>43W</u> R <u>15W</u>	<u>10</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Dec 15 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(18) Quarter corner common to Sections 22-23. Corner reestablished by single proportionate measurement to the original record in 1972 by F.J. Bray, RLS. Set 1" iron pipe with 4" aluminum cap. 18" W.Pine N86E (mag.) 25.8', 6" B.Cherry N22E (mag.) 15.4'.
 (10-Sec. 23) South 1/16 corner between Sections 22-23. Established in 1972 by F.J. Bray, RLS. 1" iron pipe with 4" aluminum cap. 9" W. Pine N61W (mag.) 15.9', 9" R.Pine S73E (mag.) 49.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(18) Recovered the 1972 monument, as described, in good condition, and at record bearing and distance from the 1972 accessories. The B. Cherry is a dead snag. The W.Pine is in good condition, now 24" DBH. Verified the position of this monument, left it in place, and marked new accessories as described below.
 (10-Sec. 23) Recovered the 1972 monument, as described, in good condition, and at record bearing and distance from the 1972 witnesses. The W.Pine N61W has been cut. The R.Pine is in good condition. Accepted the monument as a careful and faithful determination of the position of the corner. Left the monument in place and marked new accessories as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(18) 1" pipe with 4" aluminum cap.	(10) 1" pipe with 4" aluminum cap.
Blazed, scribed, and set measuring nails	Blazed, scribed, and set measuring nails
in the following:	in the following:
12" Maple West 44.8' "1/4S N8T"	10" W.Pine N35E 39.75' "S1/16 BT"
8" Aspen S03E 31.8' do	7" J.Pine N58W 60.1' do
8" Balsam S50W 22.5' do	7" W.Pine N52E 37.5' do
The 1972 witness:	the 1972 witness:
24" W.Pine N89E 26.4' "1/4S"	14" R.Pine S72E 49.7' "S1/16"
Bearings are magnetic. Dist to nail	Bearings are magnetic. Dist to nail
w/tag. Placed squared and scribed cedar	with tag. Placed 3" squared and scribed
post adjacent.	cedar post adjacent.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 3/21/00

For the Michigan Department of Natural Resources - Forest Management Division