

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft	Located in:	Corner Code #
(County)		
1. Public Land Survey	T <u>43N</u> R <u>15W</u>	<u>J9</u>
	T <u>43N</u> R <u>15W</u>	<u>K8</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

K8 Dec 17 1998
 J9 Dec 07 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (J9) Quarter corner common to Sections 23-26. Reestablished by single proportionate measurement to the original record in 1972 by F.J. Gray, RLS. 1" iron pipe with 4" aluminum cap. 6" W. Pine N08W 31.6', 8" J. Pine S46W 8.7'.
 (K8) Quarter corner common to Sections 23-24. Reestablished by single proportionate measurement to the original record in 1972 by F.J. Gray, RLS. 1" iron pipe with 4" aluminum cap. 6" J. Pine N65W 19.1', 7" J. Pine S29W 3.2'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (J9) Recovered the 1972 monument as described, in good condition, and at record bearing and distance from the 1972 accessories, both recovered in good condition. Left the monument in place and made new witnesses as described below.
 (K8) Recovered the 1972 monument as described, in good condition, and at record bearing and distance from the 1972 accessories. The J. Pine SW is now a stump. The J. Pine NW is in good condition. Left the monument in place and made three new accessories as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (J9) 1" pipe with 4" aluminum cap. Blazed, scribed, and set measuring nails in the following:
 14" W. Pine N75W 39.35' "1/4S NBT"
 6" W. Pine N71E 47.45' do
 The 1972 witnesses:
 12" W. Pine N05W 31.95' "1/4S"
 14" J. Pine S42W 9.15' do
 Bearings are magnetic. Dist to nail with tag. Placed a squared and scribed cedar post adjacent.

(K8) 1" pipe with 4" aluminum cap. Blazed, scribed, and set measuring nails in the following:
 12" J. Pine S59W 34.05' "1/4S NBT"
 5" J. Pine N55E 34.9' do
 7" J. Pine East 41.5' do
 The 1972 witness:
 10" J. Pine N61W 19.35' made new BH blz.
 Bearings are magnetic. Dist to nail with tag.



Signed by Stephan J. Szyszkoski Date 3/21/00
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division