

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T <u>43N</u> R <u>15W</u>	<u>J8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>23</u> T <u>43N</u> R <u>15W</u>	<u>12</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Dec 17 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		24			
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- (J8) Center of Section 23. Corner not established in the original survey. Found no subsequent record.
- (12-Sec. 23) South 1/16 corner, Section 23. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (J8) Established the corner at the intersection of straight lines connecting opposite 1/4 corners. At the position for the corner I placed a 1" ID x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.
- (12-Sec. 23) Established the corner midway and on a straight line between Quarter corner 1325.65' south and Center of Section 1325.65' north. At the position for the corner I placed a 1" ID x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| (J8) 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails with tags in the following: | (12) 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following: |
| 24" W. Pine S70W 101.85' "CS BT" | 8" R. Pine S82W 28.55' "S1/16 8T" |
| 24" W. Pine S88W 102.95' do | 12" R. Pine S43W 35.0' do |
| 10" Tamarack N84W 107.65' do | 8" R. Pine S30W 28.3' do |
| 14" R. Pine N26E 132.85' do | 8" R. Pine S12W 30.0' do |
- Bearings are magnetic. Distances are to nail with tag. Placed squared and scribed cedar post adjacent. Corner lies in marsh.
- Bearings are magnetic. Distances are slope distances and are to measuring nail w/tag. Squared and scribed cedar post adjacent.



Signed by Stephan J. Szyszkoski Date 3/21/00
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division