

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft
 (County)

Located in:

Corner Code #

1. Public Land Survey	T <u>43N</u> R <u>15W</u>	<u>C9</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Dec 08 1999

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9		●										
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(C9) Corner common to Sections 19-20-29-30. Reestablished by double proportionate measurement and recorded in 1969 by F.J.Bray, RLS. 1" iron pipe with 4" aluminum cap. 8" J.Pine N41W 101 links, 8" J.Pine S36W 77.5 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C9) Recovered the 1969 monument, as described, in good condition, and at record bearing and distance from the two 1969 NBTs, both recovered in good condition. Left the monument in place and made new accessories as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C9) Found 1" pipe with 4" alum. cap.
 Blazed, scribed, and set measuring nails in the following:
 14" J.Pine N39W 66.9' "S19 NBT"
 14" J.Pine S40W 51.4' "S30 NBT"
 14" R.Pine N62E 99.65' "S20 NBT"
 12" R.Pine S21E 30.5' "S29 NBT"
 3" R.Pine fence post adjacent. Bearings are magnetic. Distances to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 5/3/00

For the Michigan Department of Natural Resources - Forest Management Division