

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

SCHOOLCRAFT
Co.

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 43 N. R. 16 E. W.	A-13 ✓
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 12, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Wood post

Y. pine 18" - S52°W - 10.08 Chs.
Tamarack 3" - N54°W - 99 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

This corner was set by projecting a line from the S.E. corner of Sec. 31 across the $S\frac{1}{4}$ cor. of Sec. 31 (both of which were set from O.B.T.s) and using a measurement from the $\frac{1}{4}$ corner which is the same proportion to the original survey record as the measurement from the S.E. section corner to the S. $\frac{1}{4}$ corner is to the original survey record.

This method was used rather than the usual double proportion because no good control could be found for several miles north, west and south and I felt this method would restore the township corner much closer to its original position than a double

proportion under these circumstances.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D.N.R. monument

Set 4" sq. cedar post - S45°E - 2.0'

Set 6" sq. red pine post - N45°W - 2.0'

D.N.R. monument for the South 1/4 corner of Sec. 31 - East - 2335.4'

9" red pine - S10°E - 582'

5" red pine - S6°E - 565'

SIGNED BY

David B. Babbitt

DATE

4-30-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)