

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N. R. 16 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sec. 20 and 29

CORNER MONUMENT 2" I.D. iron pipe with 2 1/2" brass cap stamped "20-1/4-29, c.c."

DATE MONUMENT PLACED AND WITNESSED Date placed unknown; re-witnessed 6/24/64

WITNESSES TO CORNER..... Jack Pine 8 N53W 15 1/2 links, "1/4 S, NBT"



do 11 S77E 18 1/2 links, "1/4 S, NBT"

do 7 S30W 31 1/2 " " "1/4 S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner located and pipe set by Carl Christensen from stumps of two original BT's, burned, poor condition, but of species, relative and absolute size, and position as given in original field notes. Also agrees well with stream crossing to east.

SURVEYOR'S SEAL

SIGNED Arthur O. Enger RLS 13581
REGISTERED LAND SURVEYOR

DATE 9/7/65

Billy D. Buckler RLS 8887

4/13/72

Billy D. Buckler