

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 43 N.R. 16 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section corner 27, 28, 33, 34

CORNER MONUMENT 2" I.D. iron pipe with 2 1/2" brass cap stamped "27, 28, 33, 34, c.c."

DATE MONUMENT PLACED AND WITNESSED Placed in 1949; re-witnessed 3/6/64

WITNESSES TO CORNER..... Red Pine 5 N3E 42 links, "S27, NBT"



Jack Pine 7 S50E 26 " "S34, NBT"

do 7 S33W 17 1/2 " "S33, NBT"

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner located and pipe set by Carl Christensen and Carl Makel from one original bearing tree, Norway Pine 10 N30E 34 links. Tree still alive in 1964, with overgrown blades and axe marks. Assisted by W. J. Wallace in re-witnessing corner.

SURVEYOR'S SEAL

SIGNED Arthur O. Enger DATE 9-17-64  
REGISTERED LAND SURVEYOR  
Arthur O. Enger  
RLS 13581