

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Schoolcraft COUNTY

44
T 43 N R 16 W


34/35 T 44 N R 16 W

DESCRIPTION OF CORNER Section corner for sections 3/2 T 43 N R 16 W

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 8/11/69, F. J. Bray and M. Burnis

WITNESSES TO CORNER..... 7" Spruce (S.34) (NBT) N 59° W, 25 links



12" W. Pine (S.35) (NBT) N 79° E, 52 1/2 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from original B.T. (tamarack 3" S 8° E, 30 links, badly rotted). Trace of rotted wood found B.T. to SW and NE. Old down wood post near. Corner found 1960 by Foresters Wallace and Enger.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE

12/11/69

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68