

Schoolcraft Co.

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. S., R. <u>16</u> E. W.	<u>B-13, C-7</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 3, 1976 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B-13 - South $\frac{1}{2}$ corner; Wood post - Y. Pine 10 - N57°E - 140 lks.;
N. Pine 3 - S40°E - 21 lks.

C-7 - N.W. Section corner - Section 20: Wood post - Norway Pine 24" - N50°W - 15 lks.
Spruce Pine 9" - S60°E - 18 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

B-13 - Found N.E. O.B.T. down and in poor condition but part of the upper face lying on the ground with some scribe marks visible - part of lower face visible near the roots but badly burned - J.P. STP. in place for S.E. O.B.T.

C-7 - Set from stub of N.W. O.B.T. showing recent axe marks but original blazes mostly burned away (24" Norway Pine - N50°W - 15 lks.) very definite stump hole in place for S.E. O.B.T.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

ALL - 1" pipe, 4" aluminum cap

B-13 - 27" W. Pine - N23°E - 100.3'; 14" R. Pine - S12°W - 69.2'; 8" W. Birch - S43°E - 24.0'.

C-7 - 6" J. Pine - S83°W - 14.95'; 23" W. Pine - N39°W - 37.5'; 5" R. Pine - N27°E - 34.2'; 13" R. Pine - S20°E - 13.1'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 2-21-79
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558