

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Schoolcraft Co.

1 Corner

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>43</u> N. R. <u>16</u> W.	<u>A-6</u>
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 11-13, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

A-6 West 1/4 Corner of Section 18. Wood Post. O.B.T.S. : Tamarack 8, N22<sup>0</sup>W, 34 links & Spruce 5, N42<sup>0</sup>E, 30 links.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

A-6 Set by extending a line from the West 1/4 Corner of Section 6, T43N R16W Southerly across a very old down and rotten Y. Pine found along the West Section Line of Section 18 with two solid slabs of wood showing very definite axe marks which were made while the tree was living. This tree was used for alignment and the North - South position determined by proportioning the distance between the West 1/4 Corner of Section 6 and the S.W. Sec. Corner of Section 31, T43N R16W.

See "Report of Survey" on back of this form.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6 D.N.R. Monument. Bearings: 18" R. Pine, S14<sup>0</sup>W, 82.0'  
5" J. Pine, S35<sup>0</sup>W, 71.3'  
8" J. Pine, N06<sup>0</sup>W, 74.3'  
12" R. Pine, N15<sup>0</sup>E, 72.0'

SIGNED BY

David B. Babbitt  
David B. Babbitt

DATE 7-18-85

SURVEYOR'S MICHIGAN REGISTRATION NO.

21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES