

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Schoolcraft Co.

3 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>43</u> N. S. R. <u>16</u> K. W.	<u>A-4, A-5, A-7</u>
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 10-15 and 9-11, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- A-4 West 1/4 Corner of Section 7. Wood Post. O.B.T.'S.; Tamarack 6, N40⁰E, 96 links & Tamarack 6, N22⁰W, 96 links.
- A-5 S.W. Sec. Cor. of Section 7. Wood Post. O.B.T.'S.: Y. Pine 10, N51¹/₂W, 2.13 Chs. & "Post in Marsh" Y. Pine 20, N40⁰E, 2.00 Chs. & Y. Pine 14, N52⁰E, 1.66 Chs.
- A-7 S.W. Sec. Cor. of Section 18. Wood Post. O.B.T.'S. Tamarack 6, N79⁰E, 69 links & Norway Pine 6, S40⁰E, 32 links & W. Pine 15, N04⁰W, 54 links & Tamarack 6, N60⁰E, 62 links.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-4 Set M.P.O.L. between the N.W. and S.W. Section Corners of Section 7.
- A-5 Set by single proportion between the West 1/4 Cor. of Sec. 6 and the West 1/4 Cor. of Sec. 18. Could not identify any of the Y. Pine obt's but all would have fallen on a small crescent shaped ridge from this position. Also, this position is in what was marsh at the time of the original survey.
- A-7 Set by single proportion between the West 1/4 Corner of Section 18 and the S.W. Section Corner of Section 31.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set D.N.R. Monument at all three corners. Bearings:

- A-4 10" R. Pine, S83⁰E, 9.25' & 5" W. Pine, N58⁰E, 10.0' & 7" R. Pine, N28⁰W, 38.6' & 6" W. Pine, S34⁰W, 15.9'.
- A-5 8" R. Pine, N75⁰E, 76.0' & 9" R. Pine, N63⁰W, 94.0' & 12" R. Pine, N11⁰W, 112.2' & 10" W. Pine, N42⁰E, 41.5'.
- A-7 6" R. Pine, N25⁰W, 28.8' & 7" R. Pine, N28⁰E, 41.9' & 5" R. Pine, S42⁰E, 12.9' & 5" R. Pine, S48⁰W, 12.5'.

SIGNED BY

David B. Babbitt
David B. Babbitt

DATE 7-18-85

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES.