

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Schoolcraft Co.

3 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>43</u> N. <u>16</u> K. _____	S. R. _____ W. _____	A-10, A-11, A-12
2. PROPERTY CONTROLLING IN SECTION _____ T. _____ N. _____ E. _____	S. R. _____ W. _____	
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. _____ E. _____	S. R. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 3-7- 19 85, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- A-10 1/4 Corner on West side of Sec. 30. Wood Post. O.B.T.'S.: Tamarack 3, N09⁰E, 87 links & Tamarack 4, S46⁰W, 82 links.
- A-11 N.W. Sec. Corner of Section 31. Wood Post. O.B.T.'S.: Tamarack 4, S60⁰E, 48 links & Tamarack 3, N50⁰E, 61 links & Tamarack 3, N25⁰E, 49 links & Tamarack 4, S61⁰E, 49 links.
- A-12 West 1/4 Corner of Section 31. Wood Post. O.B.T.'S. Tamarack 6, S06⁰W, 128 lks. No other near.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-10 Set by single proportion to the G.L.O. Record between the West 1/4 Corner of Section 18 and the S.W. Section Corner of Section 31.
- A-11 Set by single proportion to the G.L.O. Record between the West 1/4 Corner of Section 18 and the S.W. Section Corner of Section 31.
- A-12 Set by single proportion to the G.L.O. Record between the West 1/4 Corner of Section 18 and the S.W. Section Corner of Section 31.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D.N.R. Monument set at all three corners. Bearings:
- A-10 10" R. Pine, N41⁰W, 42.7' & 6" J. Pine, N68⁰E, 14.5' & 8" J. Pine, S16⁰E, 24.4' & 7" J. Pine, S30⁰W, 11.6'.
- A-11 10" J. Pine, S31⁰E, 326.0' & 10" J. Pine, S41⁰E, 347.8' & 12" R. Pine, S47⁰E, 311.9' & 8" J. Pine, S70⁰E, 263.6'.
- A-12 12" R. Pine, S49⁰E, 132.68' & 10" J. Pine, S06⁰W, 111.56' & 12" R. Pine, S17⁰W, 82.82' & 6" J. Pine, S36⁰W, 70.08'.

SIGNED BY David B. Babbitt DATE 7-18-85
 David B. Babbitt

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558 (SEAL)