

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Schoolcraft</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>16W</u>	<u>B-9, C-9, C-10.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Babbitt, in a field survey on 1/7/87, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- B-9. North ¼ corner of Section 30. Wood post. 5" tamarack, N15E, 16 Lks.  
5" tamarack, S40W, 15 Lks.
- C-9. NE section corner of Section 30. Wood post. 4" tamarack, N67E, 25 Lks.  
6" spruce, S31W, 1.12 Chs.
- C-10. East ¼ corner of Section 30. Wood post. 3" tamarack, N35E, 2 Lks.  
4" birch, S50W, 11 Lks.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- B-9. Set by single proportion to the GLO record between the NE and NW section corners of Section 30.
- C-9. Set by double proportion to the GLO record using section corners 1 mile south, 1 mile west and 1 mile north and the ¼ corner ½ mile east.
- C-10. Set MPOL between the NE and SE section corners of Section 30. This corner falls on a relatively narrow N-S pine covered ridge in marsh.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |                              |                        |                              |
|------------------------------|------------------------|------------------------------|
| B-9. 11" j.pine, N60W, 34.3' | C-9. DNR Monument      | C-10. 10" r.pine, N7W, 38.0' |
| 7" r.pine, N73W, 88.0'       | 11" w.pine, N7W, 96.0' | 13" r.pine, N59E, 14.8'      |
| 3" w.pine, N54W, 71.9'       | 5" w.pine, S86E, 39.2' | 4" spruce, S44E, 16.8'       |
| 5" r.pine, N22W, 95.6'       | 7" w.pine, S72E, 42.4' | 7" spruce, S20W, 15.1'       |
|                              | 7" w.pine, S22W, 64.4' |                              |

Signed by David B. Babbitt Date 1-27-87

Surveyor's Michigan License No. RLS 21558