

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft
(County)

Located in:

Corner Code ~~##~~

- | | | |
|------------------------------------|---------------------------|--------------------|
| 1. Public Land Survey | T <u>43N</u> R <u>16W</u> | <u>C-11, C-12.</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, David Babbitt, in a field survey on 12/8, 19 86, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-11. NE section corner of Section 31. Wood post. Tamarack 4", N67W, 37 Lks.
 W. Pine 8", S56E, 1.79 Chs.
- C-12. East 1/4 corner of Section 31. Wood post. 8" w.pine, S3E, 22 Lks.
 No other tree near.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-11. Set from probable OBT, remains of w.pine blow down, on narrow point of higher ground in marsh. Tree is badly burned and rotted but there is no other w. pine near. This point is less than a foot off the proportionate position N&S using section corners 1 mile south and 2 miles north which were set from OBT's. Measurement to the section corner 1 mile west is 30' longer than record but moving this section corner west would cause the SE OBT to fall in an area which is now pure marsh grass. The possibility of an 8" w.pine growing there is highly unlikely. This corner falls on the southwesterly edge of a somewhat circular marsh about 300' in diameter almost entirely surrounded by higher ground within the generally marsh area.

C-12. Set MPOL between the NE and SE section corners of Section 31. This corner falls in open marsh with no trees near it. All NBT's are on islands of higher ground in marsh.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|-------------------------|---|
| C-11. DNR Monument | C-12. DNR Monument |
| 5" spruce, S80W, 16.1' | 26" w.pine, on ctr. small island N45W, 320' |
| 7" j.pine, S3E, 64.5' | 8" j.pine, N84W, 346½' |
| 6" spruce, S57E, 113.8' | 9" r.pine, S31W, 400' |
| 4" r.pine, S46E, 119.6' | 11" r.pine, N26E, 437½' |

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by David B. Babbitt Date 1-27-87

Surveyor's Michigan License No. RLS 21558