

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 43N R 16W	F1
	T 44N R 16W	F13
	T _____ R _____	(same corner)
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1						●							
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 05/19/2011 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F1) Quarter corner common to Section 4 T43N-R16W and Section 33 T44N-R16W. 1841 - Established by Wm.A.Burt Deputy Surveyor midway and on the Township Line between Section corners 40.00 chains east and west. Set post. Beech 10" N47E 34 links, Hemlock 16" N52W 13 links. 2007 - Michael Peterson PS reestablished this corner (as well as corners B1, C1, D1, E1, G1, and H1) by single proportionate measurement between corners A1 and I1. Set aluminum county monument. 12" W.Pine N10E 15.40', 13" W.Pine S70E 23.52', 8" W.Pine N80W 28.60', 11" W.Pine S52W 29.57', carsonite post South 1.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F1) The original post and accessories were not recovered. Found the 2007 monument and witnesses of record at an erroneous position, S89 deg. 32'08"W 269.63' from a position midway and on the Township line between monumented section corners E1 and G1, both of record. With Mr. Peterson's approval, the 2007 monument and witnesses were destroyed and defaced. I reestablished the position for the corner midway and on the curved Township line between Section corner E1 S89 deg. 28'34"W 2634.86' and Section corner G1 N89 deg. 28'07"E 2634.86'. All bearings stated in this paragraph are referenced to grid north, Michigan State Plane Coordinate System of 1983.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F1) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 10" Maple N08E 10.8' mrkd "1/4S NBT"
 10" W.Pine N85W 34.05' do
 9" Maple S05E 16.85' do
 8" Maple in clump S37E 23.84' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 06/15/2011
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Forest Management Division