

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

|                                       |                         |               |
|---------------------------------------|-------------------------|---------------|
| Schoolcraft                           | Located In:             | Corner Code # |
| (County)                              |                         |               |
| 1. Public Land Survey                 | T _____ R _____         | _____         |
|                                       | T _____ R _____         | _____         |
|                                       | T _____ R _____         | _____         |
| 2. Property Controlling in Section    | S 20 T 43N R 16W        | 5             |
|                                       | S 8 T 43N R 16W         | 4             |
|                                       | S _____ T _____ R _____ | _____         |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____ | _____         |
|                                       | S _____ T _____ R _____ | _____         |
| 4. Lot No. _____, Recorded Plat _____ |                         |               |
| 5. Private Claims                     |                         |               |

Register of Deeds Stamp & File Number

|    |    |   |    |   |    |   |    |   |    |   |    |   |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 10 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

I, Stephan J. Szyszkoski, in a field survey on 4 10/25/2011 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(5-Sec. 20) North 1/16 corner, Section 20. Not previously monumented.

(4-Sec. 8) Northwest 1/16 corner, Section 8. Not previously monumented.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(5-Sec. 20) Established the position for the corner midway and on a straight line between Quarter corner D7 1328.48' north and Center of Section 20 1328.48' south. Note: The monuments for Government corners C8, E8, and D7, placed in 2007 for Schoolcraft County Remonumentation, were discovered to have been placed in erroneous positions. The position for the 1/16 corner herein described was calculated using the proper positions for these corners, based upon the method of reestablishment described in the certificates of record, L5 P453-4 and L5 P397. Schoolcraft County Remonumentation has expressed their intention to correct the positions of the monuments for C8, E8, and D7.

(4-Sec. 8) Established the position for the corner at the intersection of straight lines connecting opposite 1/16 corners.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(5) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 10" R.Pine N70E 3.95' mrkd "N1/16 BT"  
 17" W.Pine S40E 22.7' do  
 7" W.Pine S25W 26.8' do  
 13" R.Pine N86W 12.5' do  
 Bearings are magnetic.

(4) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 6" R.Pine S37W 7.8' mrkd "NW1/16 BT"  
 11" R.Pine N42W 9.9' do  
 5" R.Pine N63E 13.25' do  
 11" R.Pine S37E 9.95' do  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 02/27/2012

For the Michigan Department of Natural Resources, Forest Resources Division

