

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 25 T 43N R 16W	5
	S 25 T 43N R 16W	8
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on 03/13/2012 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:**
- (5-Sec. 25) North 1/16 corner, Section 25. Not previously monumented.
 - (8-Sec. 25) West 1/16 corner of Section 25. Not previously monumented.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**
- (5-Sec. 25) Established the position for the corner midway and on a straight line between Quarter corner L9 1324.72' north and the intersection of Quarter lines of Section 25 1324.72' south.
 - (8-Sec. 25) Established the position for the corner midway and on a straight line between Quarter corner K10 1326.79' west and the intersection of Quarter lines of Section 25 1326.79' east.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- | | |
|---|--|
| <ul style="list-style-type: none"> (5) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 12" Maple N66E 22.0' mrkd "N1/16 BT" 6" J.Pine N36E 24.2' do 7" J.Pine N67W 37.7' do 7" J.Pine N14E 4.05' do Set sq'd Pine post adjacent. Bearings are magnetic. | <ul style="list-style-type: none"> (8) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 10" R.Pine N81W 3.0' mrkd "W1/16 BT" 11" R.Pine N27E 15.15' do 11" R.Pine N78E 15.9' do 9" R.Pine S17E 5.65' do Set sq'd Pine post adjacent. Bearings are magnetic. |
|---|--|

Signed by *Stephan J. Szyszkoski* Date 05/23/2012
 Surveyor's Michigan License No. 33986



For the Michigan Department of Natural Resources, Forest Resources Division

47522
47523