

SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED

DATE 11/12/97

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &  
REMONUMENTATION

JAN 21 1998

SECTION \_\_\_\_\_

For corners in

Schoolcraft Located In: Corner Code #  
(County)

- 1. Public Land Survey T42NR16W  
T43NR16W K-1  
K-13 ✓  
T\_\_\_R\_\_\_  
T\_\_\_R\_\_\_
- 2. Property Controlling S\_\_\_T\_\_\_R\_\_\_  
in Section S\_\_\_T\_\_\_R\_\_\_
- 3. Miscellaneous S\_\_\_T\_\_\_R\_\_\_  
Property in Sec. S\_\_\_T\_\_\_R\_\_\_

Received & Filed this 9 day of  
Dec. 1997 at 4:04 PM  
Sigrid I. Hedberg  
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

Thomas P. O'Brien, in a field survey on Nov. 24, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- K-1 NE Corner Section 2  
June 3, 1841 - William A Burt D.S. set corner post.  
Hemlock 12 N32E 19 do 18 N35W 21  
August 10, 1850 - Algernon Merryweather D.S. corner 1&2 North Boundry.  
Soft Maple 8 S41W 27 lks. Hemlock 18 S68E 33 lks.  
July 22, 1969 - Frank J. Bray R.L.S. set corner " on line and the single proportioned measurement between the town corner one mile to the East and 1/4 corner 1/2 mile to the West." LCRC recoded Liber 3, page 174.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-1 Nov. 24, 1997 - Thomas P. O'Brien P.S. recovered a 1/2" iron bar w/cap 27447 set in a monument box in the centerline of M-94. Witnesses found verify corner location as set by Frank J. Bray on July 22, 1969.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-1 1/2" iron bar with cap #27447 in monument box.  
Witnesses: (Fd.) 17" R. Pine-S38°E - 89 lks. (Fd. M.D.O.T. tag 59.15')  
(Fd.) 16" R. Pine-N46°E - 138 " (Fd. M.D.O.T. tag 91.55')  
NBT. 18" W. Pine-S51°W - 120.20'  
NBT. 10" W. Pine-N38°W - 80.40'  
Carsonite Post -N86°W - 40.00'

*Thomas P. O'Brien*

Signed by Thomas P. O'Brien P.S.

Surveyor's Michigan License No. 21274

Date November 25, 1997

