

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Schoolcraft

(County)

Located In:

Corner Code #

1. Public Land Survey	T	R	_____
	T	R	_____
	T	R	_____
	T	R	_____
2. Property Controlling in Section	S <u>33</u>	T <u>43N</u> R <u>16W</u>	<u>6</u>
	S <u>33</u>	T <u>43N</u> R <u>16W</u>	<u>7</u>
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Aug 18 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (6-Sec. 33) Northeast 1/16 corner, Section 33. Not established in the original survey.
 (7-Sec. 33) North 1/16 corner between Sections 33-34. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(6-Sec. 33) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
 (7-Sec. 33) Established the corner midway and on line between Section corner 1322.25' north and Quarter corner 1322.25' south. The corner lies on the west side of a small pond.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(6) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 6" W.Birch S73E 7.2' "NE1/16 BT" 6" Balsam S02W 14.45' do 10" Spruce N88W 9.1' do 4" Balsam N22E 2.1' do Bearings are magnetic. Distances are to nail with tag.	(7) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 4" Spruce S42W 203.6' "N1/16 BT" 4" J.Pine S51W 209.65' do 3" Spruce S27W 265.2' do 10" Tamarack S10E 266.75' do Bearings are magnetic. Distances are to nail with tag.
---	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 9/14/04