

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Schoolcraft

(County)

Located In:

Corner Code #

1. Public Land Survey	T 43N R 16W	F11
	T 43N R 16W	D11
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Aug 10 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- (F11) Quarter corner common to Sections 28-33. 1850 - Established by A.Merryweather: [east] Corrected bet. Sec. 28 & 33...40.00 1/4 post. S.Pine 5" S18E 15 links, Spruce Pine 6" N37W 18 links.
- (D11) Quarter corner common to Sections 29-32. 1850 - Established by A.Merryweather: East corrected bet. Sec. 29 & 32...40.00 1/4 post. Tamarac 3" N72W 38 links, Spruce Pine 6" S80E 86 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (F11) The original post and accessories were not recovered. Reestablished the corner by single proportionate measurement to the original record between section corners 2654.72' east and west.
- (D11) The original post and accessories were not recovered. Reestablished the corner by single proportionate measurement to the original record between Section corners 2654.32' east and west. The corner falls in a wet marsh with a clear-cut to the south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| (F11) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
3" J.Pine S80E 34.2' "1/4S NBT"
3" J.Pine S84W 23.5' do
3" J.Pine S27W 44.7' do
3" J.Pine N04E 25.95' do
Set cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. | (D11) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:
8" dead Spruce S68W 18.05' "1/4S NBT"
5" dead Spruce N58W 16.55' do
6" dead Spruce N81E 30.3' do
8" W.Pine S19E 92.7' do
Bearings are magnetic. Distances are to nail with tag. |
|---|---|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 9/14/04