

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Schoolcraft
 (County)

Located In:	Corner Code #
T <u>43N</u> R <u>16W</u>	<u>D13</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
2. Property Controlling in Section	S <u>32</u> T <u>43N</u> R <u>16W</u>
S _____ T _____ R _____	<u>16</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____
S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Aug 17 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

(D13) Quarter corner common to Section 32 T43N-R16W and Section 5 T42N-R16W. 1841 - Established by Wm Burt: West on South Side Section 32...40.00 Set qr. Section post. N.Pine 8 N50E 101 links, No other near. ...80.00 Set post corner Sec. 31 & 32.
 (16-Sec. 32) East 1/16 corner between Section 32 T43N-R16W and Section 5 T42N-R16W. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D13) The original post and accessory were not recovered. Reestablished the corner by single proportionate measurement to the original record on the curved township line between Section corners 2636.89' east and west. The corner falls in an open marsh.
 (16-Sec. 32) Established the corner midway and on the curved township line between Section corner 1318.44' east and Quarter corner 1318.44' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D13) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:	(16) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:
10" J.Pine N85E 264.75' "1/4S N8T"	6" Spruce S32E 3.95' "E1/16 8T"
10" J.Pine N60E 151.35' do	8" Balsam S57W 13.45' do
8" J.Pine S75E 185.35' do	4" Spruce S04W 19.8' do
6" Tamarack S63E 178.45' do	6" Balsam N03W 13.65' do
Set cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	Set cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 9/10/04