

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Schoolcraft

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>43N</u> R <u>16W</u>	<u>F13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>33</u> T <u>43N</u> R <u>16W</u>	<u>8</u>
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

8 Aug 18 2004

F13 Jul 28 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

(F13) Quarter corner common to Section 33 T43N-R16W and Section 4 T42N-R16W. 1841 - Established by Wm. Burt: West on South side Sec. 33 ...40.00 Set qr. Section post. N.Pine 3 N61E 117 links, N.Pine 5 N5W 69 links. ...80.00 Set post cor. Sec. 32 & 33. (8-Sec. 33) West 1/16 corner Section 33. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F13) The original post and accessories were not recovered. Reestablished the corner by single proportionate measurement to the original record on the curved township line between Section corners 2636.89' east and west. (8-Sec. 33) Established the corner midway and on a straight line between Quarter corner 1322.87' west and Center of Section (unmonumented) 1322.87' east. The corner falls in the center of a trail road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F13) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:	(8) Set 1"IDx36" I.pipe with plastic cap, buried. Blazed, scribed, and set measuring nails in:
4" J.Pine S17W 18.55' "1/4S N8T"	12" J.Pine S12W 21.0' "W1/16 8T"
4" Tamarack S20E 30.05' do	10" J.Pine N64E 24.7' do
5" J.Pine N76E 57.4' do	10" J.Pine N73W 41.4' do
4" Tamarack N01W 40.5' do	6" J.Pine S68W 29.3' do
Bearings are magnetic. Distances are to nail with tag.	Set location tag on post 16' north.
	Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 9/14/04