

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T43N R 16W</u>	<u>I4</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
4. Lot No. <u> </u> , Recorded Plat <u> </u>		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on Oct. 25, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(I4) Quarter corner common to Sections 10 and 11. 1850 - Established by A.Merryweather, Deputy Surveyor, midway and on the Section line between Section corners 40.00 chains north and south. Set post. Bearing trees: Beech 10 N45W 18 links, Sugar 6 S47E 17 links. 1975 - recorded by Thomas P. O'Brien RLS: Set by single proportionate measurement between NE and SE corners of Sec. 10. Set 1/2" iron bar with RLS 21274 cap. Bearing trees: 10" Maple N85E 60.3', Power Pole S15E 7.75', SE corner house N50W 38.3'. According to the Schoolcraft Co. Rd. Commission, the county road between Sections 10 and 11 (Southside Road) has been in use since approx. the 1930's. However, no records of the survey of this road, if they exist, are available.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(I4) The original post and accessories have been destroyed by road construction. Found a 1/2" or 5/8" dia. iron bar with cap #50454 (Dustin Taylor PS), in the 1975 position (this may be the 1975 monument with a new cap), which I did not accept as marking the position for the corner. Accepted the centerline of the county road (which has been in existence since the 1930's) as the best available evidence of the easting of the original corner and reestablished the position for the corner in said centerline of the paved county road and midway between Section corner I3 (as monumented and recorded by the undersigned) 2635.30' north and Section corner I5 2635.30' south.

NOTE: in a meeting held on Nov. 7 2007, the Schoolcraft County Remonumentation Program Peer Review Group approved, in accordance with P.A. 345 of 1990, the previous 1975 position of record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(I4) Set 5/8" ID iron bar with plastic cap stamped "MICH DNR LS33986" in the paved road. Set measuring nail with MDNR tag in the side of the following trees:
15" twin Maple N22E 61.0' mrkd "1/4S NBT"
16" Maple N85E 26.82' do
10" Maple S44E 46.86' do
Power Pole #9 S84W 37.42' nail/DNR tag
Set carsonite post 25' east.
The found iron/cap #50454 is N84W 38.44'
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 11/13/07

Surveyor's Michigan License No. 33986