

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>16W</u>	<u>I9</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File
Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

Jan 11 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I9) Corner common to Sections 22-23-26-27. 1956 - Reestablished by G.A.Shadko RLS by double proportionate measurement. Set 4"x42" concrete-filled iron pipe with brass cap. Twin Red Maple 3 S19-00E 32.0', Red Maple 3 N40-45E 27.1'. 1982 - recorded by Thomas P. O'Brien RLS who found and accepted the 1956 Shadko monument and made witnesses: 18" Maple S30W 61.4', 10" Maple S54E 49.1'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I9) Found and accepted the 1956 monument in good condition and at record bearing and distance from the 1982 witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I9) Fd. 4" concrete-filled iron pipe with Michigan Dept. of Conservation brass cap. Set measuring nails in:
 14" Maple S33W 61.4' mrdk "S27 NBT" *
 12" Maple S50E 49.3' "S26 NBT" *
 12" Maple N86E 47.6' "S23 NBT"
 8" W.Pine N12W 22.7' "S22 NBT"
 Bearings are magnetic. Distances are to nail with tag. * denotes 1956 NBT.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 12/19/06

For the Michigan Department of Natural Resources, Office of Land and Facilities