

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>16W</u>	<u>112</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T <u>43N</u> R <u>16W</u>	<u>6</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

6 Mar 28 2006  
 I12 Jun 19 2006

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(I12) Quarter corner common to Sections 34 and 35. 1850 - Established by A.Merryweather, Deputy Surveyor: S9'E corrected between Sec. 34 & 35 ...40.00 1/4 post. Cedar 12 in. N19W 9 links, Cedar 6 in. S64E 19 links. ...80.00 Section corner. Found no subsequent record.  
 (6-Sec. 26) Northeast 1/16 corner, Section 26. 1982 - Established by Thomas P. O'Brien RLS. Set 1/2" iron bar. 8" Jack Pine S31E 42.7', 6" W.Pine N11W 42.9'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I12) The original post and accessories were not recovered. Reestablished the corner by single proportionate measurement to the original record, on the Section line and midway between Section corners 2658.58' north and south.  
 (6-Sec. 26) Found and accepted the 1/2" iron bar of record at the intersection of straight lines connecting opposite 1/16 corners. Found the 1982 witness trees at record bearing and distance. The J. Pine is in good condition. The W.Pine has been cut.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I12) Set 1"IDx36" I.pipe with 4" alum. cap. Set measuring nails in:	(6) Found 1/2" iron bar. Set measuring nails with tags in:
8" Cedar N53E 9.82'    mrdk "1/4S NBT"	6" J.Pine N16E 31.5'    mrdk "NE1/16 BT"
16" Cedar N89E 8.55'    do	10" W.Pine S41W 44.7'    do
13" Cedar N10E 14.7'    do	8" J.Pine S08E 47.85'    do
11" Cedar S83W 20.75'    do	10" J.Pine S26E 42.6'    do

Bearings are magnetic. Distances are to nail with tag.                      Bearings are magnetic.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 12/6/06

For the Michigan Department of Natural Resources, Office of Land and Facilities