

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T43N R 16W	J3
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3										●			
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on Oct. 30, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J3) Quarter corner common to Sections 2 and 11. 1850 - Established by A.Merryweather, Deputy Surveyor, midway and on the Section line between Section corners 40.00 chains east and west. Set post. Bearing trees: Spruce 8 S75W 9 links, Balsam 4 N25E 7 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J3) The original post and accessories were not recovered. Reestablished the position for the corner as follows: Reestablished the Northing on the Section line between Section corner I3 and Section corner K3. For Easting, extended the centerline of the existing county road running along the south 1/2 mile of the N-S 1/4 line of Section 11, north to intersect with the Section line. From this position for the corner the northerly extension of the C/L of the county road between Sections 10 and 11 (position monumented October 25, 2007 and recorded as corner code I3 by the undersigned) is 2637.43' west. This close agreement to the GLO record and conformance to the C/L of the county roads to the south constitute the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J3) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 5" Cedar N34E 3.21' mrkd "1/4S NBT"
 6" B.Spruce S14W 3.23' do
 5" Cedar S35E 16.23' do
 8" Cedar N44W 13.83' do
 Set carsonite post 1.0' north.
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 11/13/07

Surveyor's Michigan License No. 33986