

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Schoolcraft</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>    </u> R <u>    </u>		
	T <u>    </u> R <u>    </u>		
	T <u>    </u> R <u>    </u>		
	S <u>11</u> T <u>43N</u> R <u>16W</u>		<u>J4</u>
2. Property Controlling in Section	S <u>11</u> T <u>43N</u> R <u>16W</u>		<u>1</u>
	S <u>    </u> T <u>    </u> R <u>    </u>		
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>		
	S <u>    </u> T <u>    </u> R <u>    </u>		
4. Lot No. <u>    </u> , Recorded Plat <u>    </u>			
5. Private Claims			

**Register of Deeds Stamp & File Number**

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2							
3									●			
4	7	8	9	10					●		12	
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on Oct. 31, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 (J4) Center of Section 11. Not established in the original survey. Found no subsequent record.  
 (1-Sec. 11) West 1/16 corner between Sections 2 and 11. Not established in the original survey. In 2005, Michael Peterson PS, placed a 5/8" iron 1318.36' N89 deg. 58'41"E from monument placed in 1975 at corner I3. (no bearing reference noted on survey drawing, project # 0405066).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 (J4) Established the corner on a straight line connecting corner K4 of record with corner I4 as monumented by the undersigned on October 25, 2007 (subsequently recorded) at its intersection with a straight line between corners J5 and J3, both of record. The position for the corner falls on the N-S C/L of the county road south, and at the extension of old fence lines running west and north.  
 (1-Sec. 11) Established the corner midway and on the Section line between Quarter corner 1318.72' east and a monument placed for I3 by the undersigned on October 25 2007, subsequently recorded, 1318.72' west. From the position thus established, I found the Peterson iron noted above to be N79 deg 08'W (true bearing), 78.29' distant, 13.88' North of the Section line, which I did not accept as marking the position for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 (J4) Set 5/8" dia. rebar with plastic cap stamped "Mich DNR LS 33986". in the west edge of the gravel driveway in which the corner falls. Set measuring nail with MDNR tag in the side of:  
 10" Spruce S33W 47.15' mrkd "CS BT"  
 11" W.Birch N68E 63.0' do  
 6" W.Birch S62E 94.25' do  
 21" Spruce N02E 43.65' nail/tag only  
 Bearings are magnetic.  
 (1) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 16" Cedar N31W 23.17' mrkd "W1/16 BT"  
 12" Cedar N43W 28.2' do  
 12" Cedar S17E 29.1' do  
 8" W.Birch S36W 26.45' do  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 11/14/07

Surveyor's Michigan License No. 33986