

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>16W</u>	<u>J9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	S _____ T _____	_____
2. Property Controlling in Section	S <u>26</u> T <u>43N</u> R <u>16W</u>	<u>7</u>
	S _____ T _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____	_____
	S _____ T _____	_____

Register of Deeds Stamp & File  
Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

J9 Mar 27 2006  
 7 Jun 19 2006

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(J9) Quarter corner common to Sections 23 and 26. 1956 - Reestablished by G.A.Shadko RLS midway and on line between Section corners 2650.0' east and west. Set 4"x42" concrete-filled iron pipe with Michigan Dept. of Conservation brass cap. 1982 - Thomas P. O'Brien found the 1956 monument in good condition, made new witnesses, and recorded same in Liber 1 of LCR Page 289. Mr. O'Brien's witnesses are: 6" W.Pine S25E 42.0', 8" W.Pine S35W 58.25'.  
 (7-Sec. 26) North 1/16 corner between Sections 25 and 26. 1982 - Established by Thomas P. O'Brien and recorded in Liber 1 of LCR, Page 289. Set 1/2" iron bar. 18" R.Pine S30W 96.05', Power Pole N69E 74.5', corner falls 4.7' E of centerline.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J9) Recovered the 1956 Michigan Dept. of Conservation monument in good condition, buried in the E-W road approximately 2' south of the C/L. the 1982 witnesses of record are still in place, in good condition, and were found at record bearing and distance. The monumented position checks well with the monumented SE and SW corners of Section 23. Accepted same as a careful and faithful reestablishment of the position of the original corner. Left the monument in place and made two new witnesses.  
 (7-Sec. 26) The 1982 monument was not recovered. Remonumented the position for the corner midway and on line between Section corner 1324.05' north and Quarter corner 1324.05' south. The 1982 witnesses check reasonably well and are described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J9) Found 4" concrete filled pipe with brass cap. Set measuring nails in: 8" J.Pine N18W 32.5' mrkd "1/4S NBT" 6" R.Pine N44E 49.9' do Found old blazes and nail/tags in: 12" W.Pine S22E 42.0' 14" W.Pine S38W 58.25' 15" W.Pine N39E 96.55' Bearings are magnetic. Distances are to nail with tag.	(7) Set 5/8"x24" iron bar with plastic cap driven flush with road surface. Set measuring nails in: 4x6 wooden post N25W 90.8' Power pole NQC440 N76E 74.65' * 14" R.Pine S22E 91.95' mrkd "N1/16 BT" 23" R.Pine S34W 96.25' do * Centerline of road 5.2' West. Bearings are magnetic. Distances are to nail with tag. * denotes 1982 BT.
--	--

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9										•			
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 12/6/06