

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>16W</u>	<u>J10</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S <u>26</u> T <u>43N</u> R <u>16W</u>	<u>12</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Jan 03 2006

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- (J10) Center of Section 26. Not established in the original survey.
- (12-Sec. 26) South 1/16 corner, Section 26. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (J10) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.
- (12-Sec. 26) Established the corner midway and on a straight line between Quarter corner 1326.68' south and Center of Section 1326.68' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |   |   |
|---|---|
| (J10) Set 1"x36" I.pipe with 4" alum.<br>MDNR cap. Set measuring nails in:<br>6" W.Pine S55E 25.1'      mrkd "CS BT"<br>10" W.Pine S30W 35.5'      do<br>6" W.Pine N23W 11.03'      do<br>6" W.Pine N83E 44.85'      do | (12) Set 1"IDx36" I.pipe with 4" alum.<br>MDNR cap. Set measuring nails in:<br>20" W.Pine N31E 7.2'      mrkd "S1/16 BT"<br>10" R.Pine S52E 15.9'      do<br>12" twin W.Pine S18E 7.87'      do<br>4" W.Pine S65W 4.45'      do |
| Bearings are magnetic. Distances are to nail with tag.  | Bearings are magnetic. Distances are to nail with tag.  |



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 12/6/06

For the Michigan Department of Natural Resources, Office of Land and Facilities