

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T43N R 16W</u>	<u>K2</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File  
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on Feb. 15, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
(K2) Quarter corner common to Sections 1 and 2. 1850 - Established by A.Merryweather, Deputy Surveyor, on the Section line between K1 and K3, 40.00 chains north of K3 and 42.89 chains south of K1. Set post with the following bearing trees: B.Ash 12" S80E 12 links, Cedar 10" West 9 links. 1964 - Corner recovered and recorded by A.O.Enger RLS who stated: [found] 2"I.D. iron pipe with 2.5" brass cap stamped "2-1/4-1, c.c" Placed in 1949, rewitnessed 11/14/1963. Corner located and pipe set by Carl Christensen and Carl Makel from one original bearing tree, Cedar 10 West 9 links. BT present in 1964, dead, standing, both faces and all marks legible. Mr. Enger made new bearing trees: Cedar 10" N76W 11 links, and Cedar 9 N35E 29 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
(K2) Recovered the 2" I.D. iron pipe monument of record, as described, in good condition, and at record bearing and distance from the 1964 NBTs (Cedar NW in good condition, Cedar NE standing dead), and at record bearing and distance from the original BT Cedar West 9 links, still standing, dead, with marks fairly visible. Accepted the monument as a careful and faithful perpetuation of the position of the original corner. The monument is about 3' north of the river bank.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
(K2) Found 2"ID I.pipe with 2.5" brass cap stamped "2-1/4-1, c.c.". Set measuring nail with MDNR tag in the side of the following trees:  
13" Cedar N75W 7.75' mrkd "1/4S" this is 1964 NBT  
10" Cedar N63E 49.45' mrkd "1/4S NBT"  
12" Cedar S53W 5.15' do  
8" Cedar S81E 28.9' do  
Set carsonite post 1.0' south  
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 11/1/07

Surveyor's Michigan License No. 33986