

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T43N R 16W	K3
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on Oct. 24, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 (K3) Corner common to Sections 1-2-11-12. 1850 - Established by A.Merryweather, Deputy Surveyor. [Does not specify monument] Bearing trees: Norway Pine 12 S25W 64 links, Norway Pine 14 N82E 70 links. Merryweather's notes show distances north 40.00 chains to Quarter corner, south 80.00 chains to Section corner, east 80.00 chains to Section corner, west 80.00 chains to Section corner. Notes also describe 5 crossings of the Stutts creek between K3 and L3. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 (K3) The original post and accessories were not recovered. Searched for and did not recover any of the GLO line trees along the north lines of Sections 11 and 12 and along the East line of Section 11. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the northing of the corner by proportionate measurement to the original record between Quarter corner 2635.45' north and Section corner 5270.67' south. Reestablished the easting of the corner at 2637.43' east of Quarter corner J3. This distance is the same as that observed between the northerly extension of the C/L of the county road between Sections 10 and 11 (position monumented Oct. 25, 2007 and recorded as corner code I3 by the undersigned) and J3. From the position thus established, I find that the Westerly three of the five Stutts creek crossings check very well at both banks with the original record. I note that the channel appears to have been affected by avulsion, some of the 1850 crossings now corresponding to slough edges. The easterly two of the five crossings do not check. It appears there was a 1 chain measurement blunder in the original survey somewhere along the line between 1 and 12, probably between 40.0 and 48.4 chains west of the Northeast corner of Section 12.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 (K3) Set 1"IDx36" I.pipe with 4" alum MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 12" R.Pine N26E 13.78' mrkd "S1 NBT"  
 19" R.Pine S61E 13.53' "S12 NBT"  
 12" J.Pine S28W 58.10' "S11 NBT"  
 15" J.Pine N74W 70.03' "S2 NBT"  
 Set carsonite post 1.0' north.  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 11/13/07

Surveyor's Michigan License No. 33986