

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u>12</u> T <u>43N</u> R <u>16W</u>	<u> L4 </u>
3. Miscellaneous Property in Sec.	S <u>12</u> T <u>43N</u> R <u>16W</u>	<u> 13 </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
4. Lot No. <u> </u> , Recorded Plat <u> </u>		
5. Private Claims		

Register of Deeds Stamp & File
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11				
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on Oct. 29, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(L4) Center of Section 12. Not established in the original survey.

(13-Sec. 12) Southeast 1/16 corner, Section 12. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(L4) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.
(13-Sec. 12) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(L4) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. (13) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of: Set measuring nail with MDNR tag in the side of:
5" Balsam N50W 8.51' mrkd "CS BT" 7" B.Spruce S75E 8.47' mrkd "SE1/16 BT"
9" Cedar S01W 14.65' do 5" B.Spruce N48E 8.08' do
4" W.Pine S38W 13.26' do 8" B.Spruce N50W 18.88' do
5" W.Pine N11E 15.50' do 7" B.Spruce S80W 21.8' do
Bearings are magnetic. Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 11/14/07

Surveyor's Michigan License No. 33986