

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T43N R 16W</u>	<u>L5</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
4. Lot No. <u> </u> , Recorded Plat <u> </u>		
5. Private Claims		

Register of Deeds Stamp & File
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on Oct. 29, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(L5) Quarter corner common to Sections 12-13. 1850 - Established by A. Merryweather, Deputy Surveyor, midway and on the Section line between Section corners 40.00 chains east and west. Set post. Bearing trees: Spruce 6 N65E 40 links, Tamarack 4 S42W 4 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(L5) The original post and accessories were not recovered. Found no evidence of the original GLO line trees on the line between Sections 12 and 13. Found no evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Section line between Section corners of record 2676.92' east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(L5) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
5" Tamarack N48W 90.17' mrkd "1/4S NBT"
4" Tamarack N32W 64.40' do
7" Tamarack N12W 78.33' do
4" Tamarack N10E 53.12' do
Set carsonite post 1.0' north.
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 11/1/07

Surveyor's Michigan License No. 33986