

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T43N R 16W	M1
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on June 6, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(M1) Corner to Townships 43-44N and Ranges 15-16W. 1841 - Established by Wm.A.Burt, Deputy Surveyor. Set post. Bearing trees: Tamarack 6 S29W 178 links, Tamarack 6 N14E 156 links. 1969 - Reestablished by Frank J. Bray RLS by double proportionate measurement to the original record between section corners two miles east, two miles west, three miles south, and 1/4 corner 2.5 miles north. Set 1" iron pipe with 4" aluminum cap. New bearing trees: 14" W.Pine S68E 93.5 links, 18" R.Pine S01W 111 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(M1) Recovered the 1969 monument in good condition and at record bearing and distance from the 1969 bearing trees. The R.Pine SW, now 22" dia., is in good condition with open BH blaze. The W.Pine SE is dead and down. Made measurements to Section corners I1, K1, M3, and M5 to check the position of the monument and found it to conform well with those corners and the record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(M1) Found 1" ID I.pipe with 4" alum. State of Michigan cap. Set measuring nail with MDNR tag in the side of:
16" R.Pine S10E 58.6' mrkd "S6 NBT"
15" W.Pine S42E 41.65' do
22" R.Pine S04W 74.4' "S1" in open 1969 blaze
5" Tamarack N05E 96.25' markd "S31 NBT"
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 11/1/07

Surveyor's Michigan License No. 33986