

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T43N R 16W</u>	<u>M4</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on Oct. 24, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(M4) Quarter corner common to Section 12 T43N-R16W and Section 7 T43N-R15W. 1841 - Established by Wm.A.Burt Deputy Surveyor midway and on the Range line between Section corners 40.00 chains north and south. Set post. Hemlock 14 S14W 33 links, W.Birch 3 N53E 13 links. 1969 - Reestablished by Frank J. Bray RLS midway and on line between section corners to north and to south. Set 1" iron pipe with 4" aluminum cap. New BTS: 8" W.Pine N41W 28 links, 18" R.Pine S16E 61.5 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(M4) Found the 1969 monument of record in good condition and at record bearing and distance from the 1969 NBTs. The R.Pine SE, now 22" in diameter, is in good condition. The R.Pine NW is dead and down. Verified the position of the monument with respect to Section corners 2642.78' south and 2638.96' north and found it to be in substantial accord with the 1969 record. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(M4) Found 1"ID I.pipe with 4" alum. State of Michigan cap. Set measuring nail with MDNR tag in the side of:
22" R.Pine S13E 41.15' 1969 NBT open blazes
14" R.Pine S52W 19.05' mrkd "1/4S NBT"
7" Spruce N08E 13.85' do
4" W.Pine N57E 27.1' do
Set carsonite post 1.0' north.
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 11/1/07

Surveyor's Michigan License No. 33986