

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

| | | |
|---------------------------------------|-------------------------|---------------|
| Schoolcraft | Located In: | Corner Code # |
| (County) | | |
| 1. Public Land Survey | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 2. Property Controlling in Section | S 23 T 43N R 16W | 3 |
| | S 23 T 43N R 16W | 8 |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims | | |

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

Jan 10 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (3-Sec. 23) North 1/16 corner between Sections 22 and 23. Not established in the original survey.
- (8-Sec. 23) West 1/16 corner, Section 23. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (3-Sec. 23) Established the corner midway and on line between Quarter corner 1325.74' south and Section corner 1325.74' north. From the corner thus established, I found a capped iron pin N01W 12.27' distant which I did not accept as marking the position of the corner.
- (8-Sec. 23) Established the corner midway and on a straight line between Center of Section 1327.60' east and Quarter corner 1327.60' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| <ul style="list-style-type: none"> (3) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 12" W.Pine S40W 22.1' mrkd "N1/16 BT" 6" W.Pine S20W 17.25' do 5" Maple S88E 10.35' do 10" W.Pine N53W 14.6' do <p>Bearings are magnetic. Distances are to nail with tag.</p> | <ul style="list-style-type: none"> (8) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 17" W.Pine N03W 23.15' mrkd "W1/16 BT" 20" W.Pine N51E 69.3' do 5" W.Pine N85W 24.8' do 8" W.Pine S47W 33.9' do <p>Bearings are magnetic. Distances are to nail with tag.</p> |
|---|---|



Signed by *Stephan J. Szyszkoski*
 Surveyor's Michigan License No. 33986

Date 12/6/06