

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft	Located In:	Corner Code #
(County)		
1. Public Land Survey	T ___ R _____	_____
	T ___ R _____	_____
	T ___ R _____	_____
	S <u>12</u> T <u>43N</u> R <u>16W</u>	<u>8</u>
2. Property Controlling in Section	S <u>12</u> T <u>43N</u> R <u>16W</u>	<u>12</u>
	S ___ T ___ R _____	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R _____	_____
	S ___ T ___ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on Oct. 29, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(8-Sec. 12) West 1/16 corner, Section 12. Not established in the original survey.

(12-Sec. 12) South 1/16 corner, Section 12. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(8-Sec. 12) Established the corner midway and on a straight line between Quarter corner 1344.73' west and Center of Section 1344.73' east.

(12-Sec. 12) Established the corner midway and on a straight line between Center of Section 1318.66' north and Quarter corner 1318.66' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(8) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.	(12) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:	Set measuring nail with MDNR tag in the side of:
8" twin Maple S69W 20.29' mrkd "W1/16 BT"	11" Maple N30W 13.05' mrkd "S1/16 BT"
8" clump Maple S02W 24.28' do	7" Balsam N70W 11.65' do
6" twin Maple S51E 18.94' do	7" Balsam S36W 7.26' do
15" Maple N82E 24.63' do	16" Spruce S75E 36.75' do
Bearings are magnetic.	Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 11/14/07

Surveyor's Michigan License No. 33986