

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T ___ R ___		
	T ___ R ___		
	T ___ R ___		
	S ___ T ___ R ___		
2. Property Controlling in Section	S 23 T 43N R 16W	12	
	S 23 T 43N R 16W	13	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___		
	S ___ T ___ R ___		
4. Lot No. _____, Recorded Plat _____			
5. Private Claims			

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Jan 11 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (12-Sec. 23) South 1/16 corner, Section 23. Not established in the original survey.
- (13-Sec. 23) Southeast 1/16 corner, Section 23. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (12-Sec. 23) Established the corner midway and on line between Quarter corner 1324.37' south and Center of Section 1324.37' north.
- (13-Sec. 23) Found and accepted a 5/8" iron rod with plastic cap by Michael Peterson PS 44292, at the intersection of 1/16 lines.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| (12) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: | (13) Found 5/8" capped iron rod. Set measuring nails with tags in: |
| 5" W.Pine N07W 11.5' mrkd "S1/16 BT" | 14" W.Pine S79E 27:17' mrkd "SE1/16 BT" |
| 5" Balsam N47E 22.15' do | 5" S. Pine N12E 8.45' do |
| 22" Y.Birch S35E 16.17' do | 11" W.Birch S08E 39.4' do |
| 9" Hemlock S82W 56.8' do | 9" Spruce S53W 52.0' do |
| Found "t" fence post N70W 14.25' | Bearings are magnetic. |
- Bearings are magnetic. Distances to trees are to nail with tag.



Signed by *Stephan J. Szyszkoski*
 Surveyor's Michigan License No. 33986

Date 12/6/06