

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	S <u>11</u> T <u>43N</u> R <u>16W</u>	<u>16</u>
2. Property Controlling in Section	S <u>11</u> T <u>43N</u> R <u>16W</u>	<u>14</u>
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File
Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

14 Oct 30 2007
16 Nov 07 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20___ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 (16-Sec. 11) East 1/16 corner between Sections 11 and 14. Not established in the original survey.
 (14-Sec. 11) South 1/16 corner between Sections 11 and 12. Not established in the original survey.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (16-Sec. 11) Found a 5/8" rebar with plastic cap placed by Michael Peterson PS#44292 at the position for the corner. Accepted same as a careful and faithful determination of the position of the corner.
 (14-Sec. 11) Established the corner midway and on the Section line between Quarter corner 1317.67' north and Section corner 1317.67' south.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (16) Found 5/8" capped iron bar. Set measuring nail with MDNR tag in the side of the following:
 12" Maple N34W 11.82' mrkd "E1/16 BT"
 16" Maple N30E 16.59' do
 14" Maple S20E 17.29' do
 9" Maple S81W 12.5' do
 Bearings are magnetic.
 (14) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 6" Cedar S27E 5.24' mrkd "S1/16 BT"
 6" Cedar N87E 2.07' do
 9" Cedar S76W 12.35' do
 8" Cedar N43W 13.84' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 11/14/07

Surveyor's Michigan License No. 33986