

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Schoolcraft Co.

3 Corners

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. <u>45</u> N. S. R. <u>13</u> E. W.	<u>M-2, M-3, M-5</u>
2. PROPERTY CONTROLLING IN SECTION.....	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-5-, 19 86, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- M-2 East 1/4 corner of section 1. OBT'S: Sugar 17, S76°E, 26 lks. & Beech 5, N39°W, 36 lks.
- M-3 Southeast sec. cor. of sec. 1. OBT'S. Fir 16, S43°E, 36 lks. & Fir 12, N43°W, 10 lks.
- M-5 Southeast sec. cor. of sec. 12 OBT'S. Cedar 10, S78°W, 36 lks. & Tam. 6, N85°E, 14 lks.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- M-2 Corner set by single proportionate measure between NE and SE corners of section 1.
- M-3 Corner set by single proportionate measure between NE corner of sec. 1 and SE corner of sec. 13.
- M-5 Corner set by single proportionate measure between NE corner of sec. 1 and SE corner of sec. 13.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

DNR monument set at all three corners.

- M-2 8" H. Maple, S67°W, 13.2' & 8" H. Maple, N3°W, 15.5' & 10" H. Maple, N31°E, 18.5' & 12" H. Maple, S84°E, 22.8'.
- M-3 7" H. Maple, East, 21.7' & 9" H. Maple, S8°E, 16.7' & 6" H. Maple, S80°W, 20.0' & 5" H. Maple, N16°W, 34.0'.
- M-5 5" Cedar, N68°W, 17.45' & 8" Cedar, N33°W, 10.0' & 6" Cedar, S59°E, 15.9' & 6" Cedar, S12°W, 12.0'.

SIGNED BY

Gerald L. Wiggins  
Gerald L. Wiggins

DATE 8-13-86

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

(SEAL)