

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Schoolcraft Co.

3 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. R. <u>13</u> W.	<u>M-7, L-5</u>
2. PROPERTY CONTROLLING IN SECTION <u>12</u>	T. <u>45</u> N. R. <u>13</u> W.	<u>14</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-6, 1986, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- M-7 Southeast Corner of Section 13. O.B.T'S: Beech 12, S68°W 27 lks. & Sugar 20, N60°E, 33 lks.
- L-5 South 1/4 Corner of Section 12 O.B.T'S: Cedar 20, N41°W, 7 lks. & Spruce 9, S18°E, 15 lks.
- 14 South 1/16 Corner on East side of Section 12. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- M-7 Found 2" X 24" Pipe set by unknown Surveyor.
- L-5 Corner set M.P.O.L. between S.W. Corner and S.E. Corner of Section 12.
- 14 Corner set M.P.O.L. between the East 1/4 Corner and S.E. Section Corner of Section 12.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

DNR Monument placed at all three corners.

- |                               |                           |                               |
|-------------------------------|---------------------------|-------------------------------|
| M-7 4" H. Maple, S15°W, 23.3' | L-5 7" Cedar, N44°W, 5.9' | 14 12" H. Maple, S33°E, 30.9' |
| 6" H. Maple, N44°W, 13.95'    | 6" Cedar, S41°W, 18.3'    | 10" R. Maple, S71°W, 12.0'    |
| 8" H. Maple, N18°E, 8.7'      | 7" Cedar, S06°E, 20.7'    | 8" H. Maple, N26°W, 21.6'     |
| 8" H. Maple, S75°E, 20.5'     | 6" Cedar, S55°E, 11.4'    | 8" R. Maple, N85°E, 18.6'     |
- Sq. Post, 10' North. Cor. buried in Center of logging road, SE-NW.

SIGNED BY

*Gerald L. Wiggins*

DATE 9-8-86

Gerald L. Wiggins  
SURVEYOR'S MICHIGAN REGISTRATION NO. 23521



FOR STATE AND UNITED STATES AGENCIES: