

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Schoolcraft Co.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. <u>2</u> , R. <u>13</u> E. <u>W.</u>	E-13, D-13
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____, R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-18, 19 82, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 13 South 1/4 cor. of sec. 31. Tam. 6" for Qr. Sec. Cor., & Cedar 5", N20°E, 10 lks.
- 13 South 1/4 cor. of sec. 32. Wood Post, Sugar 10", N15°E, 24 lks. & Fir 6", N65°W, 6 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 13 Set D.N.R. Mon. in roots of Tam. stp. Cedar stp. very rotten but overgrowth around part of lower face is still visible, N20°E, 10 lks. distant. Old notes of a Seney Refuge Boundary Survey done in 1936 note these two stumps stating that the cedar stp. was 2 1/2' high marke "S", I believe what they saw was the "B" part of "B.T." with part of the scribing weathered off. No mon. was set at that time.
- 13 Found flat iron bar set by unkwon person, but it is in the center line of an E-W road in line with an old fence and field bdry. south. Measurements east and west to known corners are very reasonable. I there for accept this iron as being the true 1/4 cor.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|------------------------------------|-----------------------------------------|
| -13 D.N.R. Monument. New Bearings: | D-13 D.N.R. Monument. New bearings: |
| 4" Cedar, N24°W, 21.45' | 3" Maple, N64°E, 45.45' |
| 9" Cedar, N16°E, 13.15' | 3" Maple, S53°E, 48.4' |
| 9" Cedar, S62°E, 29.7' | 6" Maple, S18°W, 17.1' |
| 10" Cedar, S01°W, 24.75' | 1" pipe of unknown origin, S53°W, 26.4' |

SIGNED BY

David B. Babbitt

David B. Babbitt

DATE 8-3-82

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: