

FOR CORNERS OF--

School Creek

LOCATED IN--

CORNER CODE NUMBER

1. PUBLIC LAND SURVEY T. 44 N. R. 13 E. W. G-12, C-9
2. PROPERTY CONTROLLING IN SECTION T. \_\_\_\_\_ N. S., R. \_\_\_\_\_ E. W. \_\_\_\_\_
3. MISCELLANEOUS PROPERTY IN SECTION T. \_\_\_\_\_ N. S., R. \_\_\_\_\_ E. W. \_\_\_\_\_
4. LOT NO. \_\_\_\_\_, RECORDED PLAT \_\_\_\_\_
5. PRIVATE CLAIMS \_\_\_\_\_

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David E. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 12-2, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- C-12 East 1/4 cor. of sec. 33. O.E.T.'S. Wood Post, Beech 12", N32°E, 19 lks. and Beech 6", S66°W, 20 lks. M.S.H.D. in 1928: "P.I. is on 1/4 Cor.", no description of point and no N.B.T.S. given but Hwy. stationing shows a dist. of 2605.1' North to the N.E. cor. of sec. 33.
- C-9 Northwest cor. of sec. 29. Wood Post, O.E.T.'S Spruce 9", N82°E, 12 lks & Fir 8", N47°W, 41 lks. Seney Refuge Edry. Survey by U.S. Bureau of Biological Survey notes a 1 1/4" pipe here which they refer to as having been set about 1939 but with no description of the method by which it was set and no N.B.T.S. noted.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-12 Set by retracing the 1928 Hwy. Dept. Survey. This position fits an average of the occupation lines North and South.
- C-9 Found 1 1/4" Iron Pipe projecting 3'+ above ground as noted in a 1960 survey by the U.S. Bureau of Biological Survey in connection with the Seney Refuge Edry. No record of how it was set but it fits the stream call 16.16 chs. South and distance East to the N. 1/4 cor. of sec. 29 which was set from an O.B.T. by Carl Christianson this is comparable to other E-W measurements in this Twp. Replaced pipe with D.N.R. Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-12 D.N.R. Monument. New bearings: S.E. Cor. Cabin, N30°W, 148.0' & Chiseled + on South end of conc. drive culvert, N10°E, 109.3' & Chiseled + on North end of conc. drive culvert, S15°E, 20.95' & Brass Tag in side of P.P., S32°W, 69.1' & Center line M-77, East, 43.5'.
- C-9 D.N.R. Monument. New bearings: 7" W. Pine, S13°E, 9.5' & 7" W. Pine, S79°W, 34.75'  
12" W. Pine, N45°W, 29.65' & 8" W. Pine, N69°W, 36.05'

SIGNED BY

David E. Babbitt  
David E. Babbitt

DATE 1-26-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY

CHIEF OF SURVEY PARTY

DATE

APPROVED AND SIGNED BY

MICHIGAN REGISTERED LAND SURVEYOR

DATE

(SEAL)