

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Schoolcraft Co.

3 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. S., R. <u>13</u> E. W.	G-13, F-13, E-13
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-4 & 10-11 & 11-10, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- C-13** Sec. Cor., Southeast sec. 33. Wood Post, OBT'S Beech 10", N62°E, 32 lks. & Sugar 6", N45°W, 15 lks. M.S.D.H.D. 1½" Shaft. 12" Elm, S65°W, 41.84' & 12" Maple, S45°W, 49.80 & 10" Maple, N60°W, 73.25'.
- F-13** South 1/4 cor. of sec. 33. Wood Post, OBT'S Sugar 14", N32°E, 40 lks. & Ironwood 6", N25°W 18 lks.
- E-13** Southwest sec. cor. of sec. 33. Wood Post, OBT'S Hemlock 20", N20°E, 18 lks. & Hemlock 14", N33°W, 40 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-13** Found 1½" Iron Bar buried in E-W dirt road. Set 5/8" re-rod and plastic RLS cap over it. M.S.H.D. NETS would fall in the clear vision area of road intersection.
- F-13** Set M.P.O.L. between the S.E. and S.W. sec. corners of sec. 33.
- E-13** Set by single proportionate measurement between the S½ cor. of sec. 32 and the SE sec. cor. of sec. 33.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-13** 5/8" re-rod W/R.L.S. cap. New Bearings: 12" R. Maple, N71°W, 137.4' & 12" H. Maple, S78°W, 135.0' & 16" H. Maple, N85°E, 113.6' & Center line M-77, East, 54.35' and corner lies in center of East - West road.
- F-13** 1" pipe W/RLS cap buried. New Bearings: 10" Ironwood, N51°E, 28.4' & 8" R. Maple, N52°W, 30.7' & 4" R. Maple, S42°W, 27.9' & 8" R. Maple, S20°W, 27.0'.
- E-13** 1" pipe W/RLS cap buried. New Bearings: 14" Hemlock, N56°E, 75.7' & 14" Hemlock, N5°E, 31.5' & 12" Hemlock, S44°W, 42.7' & 10" Cedar, S52°E, 24.5'. Corner lies in road.

SIGNED BY

David B. Babbitt
David B. Babbitt

DATE 1-26-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: