

**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**

Schoolcraft Co.

3 Corners.

FOR CORNERS OF --:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. <u>13</u> E. <u>W.</u>	E-9, C-11, D-11
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ E. _____ S., R. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S., R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-4 & 12-7 & 12-7, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- E-9 N.W. Sec. Cor. of Sec. 28. Wood Post, OBT'S Sugar 8", N62°W, 10 lks. and Sugar 18", S65°E, 13 lks.
- C-11 N.W. Sec. Cor. of Sec. 32. Wood Post, OBT'S Sugar 14", N44°W, 28 lks. and Sugar 12", S44°E, 24 lks.
- D-11 North 1/4 Cor. of Sec. 32. Wood Post, OBT'S Sugar 12", N41°E, 36 lks. and Beech 8", S69°W, 24 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-9 Set in line with center line of roads North and East. This position is reasonable with existing corners in all four directions and the accepted corner position by local residents. It is, therefore accepted as the best available evidence of the true corner position.
- C-11 Set by double proportionate measurement using sec. cors. 1 mile North, 1 mile South and 2 miles East and the 1/4 cor. 1/2 mile West.
- D-11 Set M.P.O.L. between the N.E. and N.W. section corners of section 32.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-9 1" pipe w/plastic R.L.S. cap buried at intersection of roads North and East. New Bearings: Tag in 18" H. Maple, S70°W, 51.9' & Tag in 10" W. Birch, S29°W, 43.85' & Tag in Power Pole, S31°E, 33.2'.
- C-11 D.N.R. Mont. 6" Maple, N46°E, 19.5' & 8" Maple, S64°E, 25.8' & 9" Maple, S32°W, 38.0' & 10" Maple, N48°W, 50.5'.
- D-11 D.N.R. Mont. 4" R. Pine, N66°W, 2.4' & 5" R. Pine, S33°E, 47.0' & 6" R. Pine, S11°W, 10.3' & 4" R. Pine, S46°W, 21.3'.

SIGNED BY

David B. Babbitt  
David B. Babbitt

DATE 1-26-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

FOR STATE AND UNITED STATES AGENCIES:

