

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Schoolcraft Co.

1 Corner

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. R. <u>13</u> E. W.	<u>E-11</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David E. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 12-20, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

E-11 Southeast cor. of sec. 29. O.B.T.'S. Wood Post, Cedar 14", N64°W, 14 lks. and Cedar 12", S45°E, 07 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

E-11 Set on a line extended from the S.E. sec. cor. of sec. 28 across a 20" Cedar stump for the line tree on line bet. secs. 28 & 33 recorded as "West 61.08 Cedar 18" in Diam." This stump is cut low and therefore shows no hack marks but it is the only one in the area large enough to have been an 18" Cedar at the time of the original Gov't Survey. The E-W position was determined by a single proportion using the sec. cor. 1 mile East and the 1/4 cor. 1 1/2 miles West. This position fits the stream call 26.38 chs. North and is reasonable for swamp calls in the area (swamp edges in most cases are not definite.).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-11 D.N.R. Monument. New Bearings: 7" Cedar, S51°W, 1.6'
8" Cedar, N47°W, 10.1'
7" Cedar, N12°W, 8.3'
8" Cedar, N67°E, 14.5'

SIGNED BY

David E. Babbitt

DATE 2-3-83

David E. Babbitt
SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: