

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Schoolcraft Co.

3 Corners

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. <u>13</u> E. S. R. _____	G-10, G-9, F-9
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-4, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- G-10 East 1/4 Cor. of Sec. 28. O.B.T.'S. Wood Post, Cedar 9", N41°E, 18 lks. and Cedar 6", S37°W, 12 lks.
- G-9 N.E. Sec. Cor. of Sec. 28. O.B.T.'S. Wood Post, Sugar 12", N24°E, 36 lks. and Sugar 12", S7°W, 13 lks. M.S.H.D., 1" pipe, Power Pole, S62°E, 71.46' & Power Pole, S50°W, 44.66' & Guard Post, N23°W, 41.42'.
- F-9 North 1/4 Cor. Sec. 28. O.B.T.'S. Beech 12", N42°E, 9 lks. and Wood Post Sugar 10", S68°W, 18 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-10 Set M.P.O.L. between the N.E. and S.E. section corners of section 28.
- G-9 Set by re-tracing M.S.H.D. survey for M-77 (Proj. #75-11).. No sign of pipe or N.B.T.S.
- F-9 Set in center of E-W road and in line with very old fence line North. Measurement to Sec. Cors. 1/2 mile East and 1/2 mile West are reasonable.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-10 D.N.R. Mont. 10" Cedar, S70°W, 89.0' & 8" Cedar, S89°W, 85.5' & 8" Spruce, N40°W, 134.0' & Center Line M-77, East, 51.5'.
- G-9 1" pipe w/plastic R.L.S. Cap. 5" Tamarack, N41°W, 112.9' & Tag in Power Pole, S48°W, 42.52' & Center Line M-77, East, 54.7'. Cor. lies in E of E-W Road.
- F-9 1" pipe w/plastic R.L.S. Cap. 14" Y. Birch, S54°E, 74.4' & 14" H. Maple, S32°W, 43.95' & 24" H. Maple, N89°W, 37.5' & Cor. lies in E of E-W Road in line with old fence North.

SIGNED BY

David B. Babbitt

David E. Babbitt

DATE 2-4-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: